

Job Filename: DG ARAGON
Job Description: Untitled

Scale: 1":29.9'

Cross-section spacing: 0.50 FT

Soil Expansion: 0%
Soil Compression: 0%
Import Soil Compression: 0%

Cut Area: 19174.3 FT2
Fill Area: 49790.8 FT2
Work Area: 72982.5 FT2

Bank Cut: 1145.7 YD3
Expanded Cut: 1145.7 YD3
Bank Fill: 2590.4 YD3
Topsoil Stripped: 1339.8 YD3
Topsoil Replaced: 650.1 YD3

Import: 1444.7 YD3
Topsoil Export: 689.7 YD3

Job Filename: DG ARAGON
Job Description: Untitled

Please note that the following information is based solely on the areas' shape and depth and without regard to Perimeters and Excluded Areas.

Subgrade Name	Area, FT2	Perimeter, FT	Volume, YD3
HD PAVING	15905.3	1169.2	589.1
LD PAVING	559.0	108.6	15.5
LD PAVING	2861.4	366.9	79.5
SIDEWALK	2249.9	658.0	41.7
CONC TRASH PAD	714.7	111.7	26.5
LD PAVING	4441.5	499.8	123.4
BLDG	10734.7	426.4	596.4

Topsoil Area, Stripped	Area, FT2	Perimeter, FT	Volume, YD3
TOPSOIL	72997.4	1305.2	1351.8

Job Filename: DG ARAGON
Job Description: Untitled

Please note that the following information is based solely on the areas' shape and depth and without regard to Perimeters and Excluded Areas.

HD PAVING - Custom Paving Section			
Asphalt	4.00 in	196.4 YD3	388.80 TON
Stone base	8.00 in	392.7 YD3	746.18 TON
LD PAVING - Custom Paving Section			
Asphalt	3.00 in	5.2 YD3	10.25 TON
Stone base	6.00 in	10.4 YD3	19.67 TON
LD PAVING - Custom Paving Section			
Asphalt	3.00 in	26.5 YD3	52.46 TON
Stone base	6.00 in	53.0 YD3	100.68 TON
SIDEWALK - Custom Concrete Slab			
Concrete	6.00 in	41.7 YD3	124.99 TON
Select fill	0.00 in	0.0 YD3	0.00 TON
CONC TRASH PAD - Custom Paving Section			
Asphalt	6.00 in	13.2 YD3	26.21 TON
Stone base	6.00 in	13.2 YD3	25.15 TON
LD PAVING - Custom Paving Section			
Asphalt	3.00 in	41.1 YD3	81.43 TON
Stone base	6.00 in	82.3 YD3	156.28 TON
BLDG - Slab - 6" concrete, 12" select fill			
Concrete	6.00 in	198.8 YD3	596.37 TON
Select fill	12.00 in	397.6 YD3	1073.47 TON

EarthWorks Elements, Materials Summary Report Date: 09/04/15 Time: 02:52 PM
Job Filename: DG ARAGON
Job Description: Untitled

Please note that the following information is based solely on the areas' shape and depth and without regard to Perimeters and Excluded Areas.

Asphalt	282.4 YD3	559.14 TON
Stone base	551.6 YD3	1047.95 TON
Concrete	240.5 YD3	721.37 TON
Select fill	397.6 YD3	1073.47 TON