

AVON			ENTER UNIT PRICE	
DESCRIPTION	QUANTITY	UNITS	UNIT PRICE	EXTENDED PRICE
<b>SOIL EROSION &amp; SEDIMENT CONTROL</b>				
INITIAL SILT FENCE	225	LF		0
INITIAL CONSTRUCTION ENTRANCE	473	SF		0
INITIAL SCL	388	LF		0
INITIAL INLET PROTECTION	8	EA		0
INITIAL CONCRETE WASHOUT AREA	192	SF		0
<b>FINAL SILT FENCE</b>				
FINAL SILT FENCE	225	LF		0
FINAL CONSTRUCTION ENTRANCE	473	SF		0
FINAL SCL	359	LF		0
FINAL INLET PROTECTION	4	EA		0
FINAL CONCRETE WASHOUT AREA	186	SF		0
ROCK SOCK 8' LONG	5	EA		0
CHECK DAM 8' LONG	5	EA		0
<b>EARTHWORK</b>				
STRIP TOPSOIL 6" THK & STOCKPILE ONSITE	1532	CY		0
GENERAL EXCAVATION-CUT TO FILL W/ COMPACTION- <b>** (BASED ON 4' BUILDING SUBGRADE ADJUSTMENT) **</b>	12638	CY		0
EXPORT EXCESS MATERIAL	11176	CY		0
ROUGH GRADE SITE	9256	SY		0
RETURN TOPSOIL TO OPEN AREAS, 6" THK	481	CY		0
EXPORT EXCESS TOPSOIL	1050	CY		0
<b>SANITARY SEWER</b>				
6" PVC SANITARY, 0-8' DP	304	LF		0
6" PVC SANITARY, 0-8' DP.- <b>OFFSITE</b>	90	LF		0
SANITARY CLEANOUT	5	EA		0
WYE CONNECTION	1	EA		0
SANITARY SERVICE TRENCH RESTORATION-NO DETAIL PROVIDED	483	SF		0
<b>STORM SEWER</b>				
CONNECTION TO GARAGE LEVEL STORM ROUTING	1	EA		0
5' DIA MANHOLE, 0-8' DP	2	EA		0
4' DIA MANHOLE, 0-8' DP	1	EA		0
TYPE 'C' INLET, 0-8' DP	1	EA		0
TYPE 'R' INLET, 0-8' DP	1	EA		0
TYPE '13' VALLEY INLET, 0-8' DP.	1	EA		0
12" PVC 0-8' DP	5	LF		0
12" RCP, 0-8' DP	65	LF		0
18" RCP, 0-8' DP.	61	LF		0
<b>WATER DISTRIBUTION</b>				
CONNECT TO EX. WATER MAIN 8"X8" WET TAP	2	EA		0
8" D.I. WATER MAIN W/CATHODIC PROTECTION	277	LF		0
6" WATER SERVICE STUB	8	LF		0
8X8 TEE W/ 6" REDUCERS	1	EA		0
FIRE HYDRANT ASSEMBLY	1	EA		0
8" 90 DEG BEND	1	EA		0
8" 22.5 DEG BEND	2	EA		0
8" GATE VALVE	2	EA		0
8" 45 DEG BEND	2	EA		0
PLUG REMOVED WATER AT TEE	1	EA		0
WATER SERVICE TRENCH REPAIR- <b>**NO DETAIL PROVIDED**</b>	97	SF		0
<b>CURB &amp; PAVEMENT</b>				
CDOT TYPE 2 CURB & GUTTER	777	LF		0
CDOT TYPE 2 GUTTER 4'-372 SF	93	LF		0
WALKING PATH ASPHALT	3924	SF		0
SAWCUT <b>** (INCLUDES SAWCUT FOR UTILITY TRENCH RESTORATION) **</b>	547	LF		0
PAVING DGA, 6" THK- <b>**NO DETAIL PROVIDED-ASSUMED THICKNESS**</b>	6027	SF		0
PAVING BASE COURSE, 4" THK- <b>**NO DETAIL PROVIDED-ASSUMED THICKNESS**</b>	6027	SF		0
PAVING SURFACE COURSE, 2" THK- <b>**NO DETAIL PROVIDED-ASSUMED THICKNESS**</b>	6027	SF		0
AMBULANCE PARKING STALL- <b>**NO DETAIL PROVIDED**</b>	1069	SF		0
CURB REPAIR STRIP 2' WIDE- <b>**NO DETAIL PROVIDED**</b>	852	SF		0